

*Blackfoot Translation of GW190814 LIGO Virgo Science Summary
(see note at end of document)*


amu?k Abatu?gwixiniip essaganistsii GW190814: axibutstsiiya gagaduusiists-spiguyis sigooxga gii anI ixumidabii o?ganstsiiya Iyinibiists

ani_k idepu*gyagyup niswigubuuudui, 2019,
nadugisduuyiixis madumanisdAsii
nyuxge-itu?gutsiisaduubyuyix nessxgatsimya mistsk
Abuduuxbiisi o?bigimskaa Iyiinapsgagii
(GW170814), nadugaya Advanced LIGO
im?gutsiisaduubyuyix miim amsgabuu?ts, anim
Hanford, Washington gii Livingston, Louisiana, gii
Advanced Virgo itu?gutsiisaduubyuyix miim Cascina,
Italy, nessxgatsimya matst*sigi* Abuduuxbiisi
o?bigimskaa Iyiinapsgagii i dutstsi ixumidabiinatsi.
mixsk LIGO-Virgo itu?gutsiisaduubyuyix
bitsioxgaduumya nuuxgl Lessxgatsimya oxgasiya_03,
itsxgatsimya iixku*dagu o?ganabii, a?~ku*danistsiwiw
nAsaguuya gii iibutstu?biya nadugaya o?ganstsiiya
Iyinibiists- amui sigooxga, gii anii xistapsxinimya.

nadugaya i tsstunnatsugabiya mu?k
utstu?guunimanuwa nitsini _gaduup GW190814
ixibisadabiya. niduxge, amui iixsugu o?ganstsiiya
Iyinibiists i-ku*sibyago spiguyi gii
stunadu~ma?gadum gii anim
matst*siga*ku*bugabessima, aganyup
madani~kuguwAstsii itsii daan essxgatsdagya
mistsk Abuduuxbiisi o?bigimskaAsts anu?k.
naduge, utspiguyis nessxgwiip amui i-ku*bugi
o?ganstsii Iyinibi aganistabi sa?gwinatsi sigooxga gyI
iixstunatsugu bugutsitsbiixiya gagadusii
ago?gwixinimya mustsk itsii_daanix nadugaya
o?ganstsiiya Iyinibiists – madesxxinibinaan.
ebuutstsiya, i tudess sagidumanistsup otsisdabitsiip
spiguyiists amustsk o?ganstsiiya Iyinibiists gii
tsai_doduya iibutstsiya itsii_daanix.

Abuduuxbiisi o?bigimskaa Iyiinapsgagi

amu?k abessatsduup Abuduuxbiisi o?bigimskaa
Iyiinapsgagi niistsi agooxtsiimaan awanisduutsiip
niixi itu?gutsiisaduubyuyix i do?gwiyiga
aganistsiists i dodagiya essdagiists, agiitsbutsdumya
agooxtsimaan iigayissximaaniists miistsk
Iyiinapsgagii nam Einstein's bisaatsjinsiimaan.
imadesxxgatsimsiists nidaku*tsxinibinaan amui
niduxge gibuma?xdudaxin issduyiists amui
GW190814 ba?tsabiiw e~gamu?suganistsii
itu?gutsiisaduumyatsix ixistsabi. GW190814
nyuuxganistsi iixku*dagu o?ganabi
nidesxxgatsibinaan anu?k xistsigui (Apstsiixisamuu
GW170817 gii GW150914). anistsiwi




sinaxin niduxge: idudu-axsabaduum Astamatsujix amustsk
agooxtsiimaan itsstiyya GW190814, nessxgatsimya miixi LIGO
Hanford (isbitstsiw). Ligo Livingston (datsigyuu), gii Virgo
(xiyuu?ts). utsidudu*buwa itssinAbya gibui issxinidaxin bitsiistuu
uudo?gabis. anii esstuumskuutsp agidabidumAdagyup
idudu-axsabaduum idAsa~pi dagyup Astamatsugi amusts
mutsinatsiists. amu?k biixihi_gi Iyiinapsgagii iixku amui
datsigyuu isstaxinya (LIGO Livingston agooxtsiimaan), anim
amu?k Iyiinapsgagii iixku*dagu.

Visit our websites:
<http://www.ligo.org>
<http://www.virgo-gw.eu>



ixstunats*iixku**dagu i_ *tsinimya* uuwapsbiix anii sinaxin *Astamatsugi* *axsabaduum* itsinAp **Figure 1**, *Astamats~tu*gi* tsa *axsabaduum* mustsk *Iyiinapsgagii* *ayu?gitsiya* *otsistsganistsii*.

gyamu?k 03, niixi LIGO-Virgo essdudabodagiya *Astamibuutsimya gyannimI ayiinapsguwa madabiix a?gigamabanistsiiw* Abuduuxbiisii o?bigimskaa oo?gutsiisaduumyatsiix. amustsk o?ganessxinimya madabiix *ayiinapsguwa itsitsiya agudumanugiya itsixinixin ido?gwissxinimya tsima i_duutstsii mu?k uutsu?guunimanuwa, gyI anistabiiw uutsu?guunimanuwa odudamitsiip*. GW190814 *ne~gamu?sessduuya* niixi madabiix Adudu *natsibu natsibusxinidaxin* *Axisdapsii oo?gutsiisaduumyatsix gyanistsii odudamitsiip mu?k “spiguyis iinaxigawestsi.” anistabanyusin niduxgaya* amustsk o?ganstsiiya Iyinibiists aganyup utss*spiguyis itsidugesstsii nyuxge* gii nisidui otsitsganistsuu anii utss*spiguyis* nam nadus, M_{\odot} . amu?k aginstabiwi mu?k “*spiguyis iinaxigawestsi”* i_tu**daya?* guminugii dapsxsaduumyam amustsk *essxgatsiipiists sigooxgaya utss*spiguyisuwa* xiuu?ts manisti_bii* nisidui M_{\odot} . amu?k *matsabanistsuu sigooxgaya spiguyis awanisduup “innA**bi**xijp”* *spiguyis iinaxigawestsi.*




sinaxin *naduge*: amuu spu?ts itu?gunimyam mu?k GW190814 *Iyiinapsgagii a?-ku*duutstsiiw*. anistsi *uutsgwinatsi* o?batstsiipiists *madumu**gunimyam idessxgatsimya niistsi agooxtsiimaan, *gyannistsi* sigumo?xinatsi o?batstsiipiists itsitsiyya *gyannyI* spu?ts uuutuu?guunisuwa .

mistapuu?ts idessxgatsiip miistsk *Iyiinapsgagii* *aku*danistsiiw* nitsuuxstuup miistsk *spiguyiists*, gii *nAsubuyapu*duumya* *nAsugabanisduumya* *niitsigubudui* *esssAsagistsii* itu?tsuwartsduumya mu?k uutsu?guunimanuwa *odudamitsiip* “NSBH.” *i_dot*sidaabidiagiya amuu o?ganstsiiya Iyinibiists *uspiguyis gagidutstsii* $3 M_{\odot}$, aganyup anis*dabi*iiw manistsuu bugutsitsbiixiya gagadusii. mu?k uutsu?guunimanuwa *a?gitstsiiw* amuu spuu?ts ina~ku*tstsii *natsibui atsutsixistdusi udaganistsi_p* (satsit sinaxin **nuuxge**). *nidutsibinaan* amustsk *Iiinapsgook*, *gyaxsabak abessatsimya*, *udayaganistsi_p* mu?k GW170817, *axistudanistsiya babusuxbiisiists Asabaduumya* gii *sta*-oyixiists *myanisdAsisixinibya isstsga*, *inoganistsii matu*gwinimya matstsigi* nuu?gitsiists Abuduuxbiisii o?bigimskAAsts.*axigamanistsii*, *udaganistsiip*, *i_tu*tsxxinimya* GW190814 *igutsitsxibistsii* mi_k GW170817 gii *agesxxinip issxgwiipiists uutsu?guunimanuwa* *Astamatsaa* (satsit xiuiu?ts) *madAdapstsiya iixgunadapsi babusuxbiisiists abatseesiiduyi*.

Astamatsaa mistsk uutu?guunimanuwa

aniiw stunatsissugu o?ganstsiiya Iyinibiists anuum *itsii*_daan utss*spiguyis* aganyup Adamaagidutstsii natsibunuuxge M_{\odot} , *niiduyaanistsiis* amustsk sigooxgaya essxgatsimya niix LIGO gii Virgo anu?k (satsit sinaxin **nuuxge**). utss*spiguyis* anI *ixa?ku?tsi* o?ganstsiiya Iyinibiists *idesstsiiw datsigaa?ts naduge* gii *ano?guts* gii **nuuxge** M_{\odot} , agitsduup itu*gidesstsii amuu stunatsissugu *nessxinuwa* bugutsitsbiixiya gagadusii, MSP J0740+6620, gii *itsida?dessti* miix *nidu?ganistsii* *spiguyiists* muxsk sigooxiya noo?gutsiisaduumya *nAbu?sa~pi_kaduumAsts babusuxbiisiists essxgamiisttsiists*. *inoganistsiiw*, *iiduutstsiiw* utss*spiguyisin* anii o?ganstsiiya Iyinibiists (*a?gamanisdabiiw* sigooxga) *i_dubitsiip* mu?k *ibuutu?biya nadugaya* bugutsitsbiixiya gagadusiix *nAnimya* mu?k GW170817.



sinaxin **nuuxge**: **amustsgogya odumu?**duup **spiguyiists nadugaya** o?ganstiyya Iyinibiists i_tu***duutstsiw** GW190814. amuu **emmixgAstsii AXIS** Astamatsugi **manistsspigii** anI **utsitsxsugu** Iyinibii, gyamu nAgesstsi **AXIS** Astamatsugi **manistsspigii** amu?k fxa?ku?tsi Iyinibii (**aganisabiiw bugutsitsbiixiya gagadusii** gyI sigooxga). anistsii subuyapsama gii **axixsinAp itstsiw Astamatsagi u?**dayagiss **Astamatsugi igamagiibuuutsduupiists** mustsk **spiguyiists** niiduyaanistsiiya amustsk agooxtsiimaan. **gyaniisti nayumuxtii matstsigi isstaxina s~bii** gii naawuu?ts a~ku*guda **niduyi agani~tu*gudaya** amustsk **a?gamiduutstsiya u?**dayagiss niitstsiw **spiguyiists.** amusta **nadugaya** itstsiw **nadugAsts nu?gitsiya** manistsinim itu?bugabistutstuwa **i?gayixxinim anii Iyiinapsgagii mu?k bisaatsinsiimaan.**

igagimaduupyia nam Einstein gii Hubble

GW190814 mis~ku***gugi** aguuutsabiiya **ido?ganop***iists amustsk istsgaabiists. gyamu?k GW190814 **igutsitsiiw adani~ku*guwAstsiwa mi_k GW190412**, **iganistsabitsiws itsiyya essbi_bugAni_gi**, gyI s~bii*igagawuya* nuu?gi**danistsiyya i_desstsiimobya** mistsk Abuduuxbiisii abatseesiiduyii **itsiyya gagidodabaniya Iyiinapsgagii**. amu?k sugabi **ogaxtsimaya ani_k bisaatsinsiimaan agayixxinimya** mistsk nuu?gi**danistsii i_desstsiimobya** omudabAsiiya Abuduuxbiisii abatseesiiduyii.

nidanisuutsiibinaan madago gageessxi axtsiinAxinimya mu?k bisaatsinsiimaan anii GW190814 gii **ni~tu*gunibinaan mu?k Iyiinapsgagii** (sinaxin **nisui**) **Astamatsugi** ixsu~ku*-Astamatsa anI_gi **i butstsiya nadugaya** sigooxgaya. inogu?gitsii, **matu*gunimIya** axsaganistaya anI sa~ku?tsi Iyinibii a?xawanisdabiiw mutst*sigi* **nomaniya awaniyya anistabiiw** sigooxga, imada**nistsiyya amu?k bugutsitsbiixiya gagadusii** gyI matst*sigi* **agitsibisatsiupi**.


amu?k GW190814, **maniw**, amu?k Abuduuxbiisii-o?bigimskaa-itstsiw issxgwiip mu?k **Hubble Constant, H_0**, anu?k **axidobuma?gu** manistsigamu?bi_p num spuu?ts. GW190814, nu?k xistsigui, i_tu*ganAsugabi-anuum Abuduuxbiisii-o?bigimskaa uutsu?guunimanuwa num spuu?ts **madAnuwanaan** matst*sigi* mistsk **babusuxbiisiists Asabaduumya** gyI **sta~oyixiists myanisAisisixiniba** isstsga. gyamu?k **idodudamapsii** spu?ts **utsiidamiit**, i-gamu?switstsiis matst*sigi* Astamatsugii anI **idodudamapsi** spu?ts **utsiidamiit bisadabi, axtsinAsatsip** a?gamayagudamapsiya o?ganessxinuwAx spu?ts **utsiidamiit** miim GW190814's itu?ganAsugabii-anuum idubobiss i_duutstsiw. agitsigigagimaduup amu?k Hubble constant axtsinAbuutsduup **o?ganAbuutsduup utomo?xinatsi asu~ku?bi, aginogessxgatsiip** miixsk matst*sigi* iists **idodudamapsi**, gyamu?k Abuduuxbiisii-o?bigimskaa tsaanitsibyuu issxgwiip. gyamu?k **oxdagubiists, idessxgwiip H_0**, aganyup matsidapsxinyup, itstsiw **75km** amustsk issxiinidaxin amustsk stunatsibyuu, aganyup iduutstsiw gii bitsiistui **essxgatsiip** Abuduuxbiisii o?bigimskaa uutsu?guunimanuwa gyamu?k matsitsiip matst*sigi*.

gyamu?k madani~ku*guwAstsii spiguyiists anii **iguma?gu gyanl iku*bugim essbumugiya ayessxgwiip** mustsk uutsu?guunimanuwa **Astamatsaa igaxnomanyup. utsitsganistsiwiw** amu?k madani~ku*guwAstsii, **aguutsitsxgunabiwiw** anI **anagu itsspiigaasaya "i_bugAni_gi"** miistsk **utsidomAda~kibowl** **axsabaduum anistsk Abuduuxbiisii** o?bigimskaa **Iyiinapsgagii**, aganyup nAdumanistsiiw ixi~gugutsgadu miixsk **Asatu*dugi agidAsApsgabada**. **ayessatsiip** miistsi matsi**duman**~ku***gutstsii-spiguyis** sigooxga **iibuutu?biyya GW190412**, **madumanabisin i_datstsiw manistbisstsiw** gii **utsitsga?sit** anii **itsi_daan nAna~ku*buniip** anistsii mats*sigi* **axsabaduuup** aniw **sbigaasa i_bugAni_gi**. gyamu?gI **nidiuumu*tsxinibinaan** Abuduuxbiisii o?bigimskaA **Assts nitsin_gadup** GW190814 i_tu***duuutstsi** aganyup nanisigubuudu **abawawa?go issduyiists axiibiisabesspsabii** **ixibisstsiw**.

o?ganstiyya Iyinibiists **aganiistiyya** bugutsitsbiixiya gagadusii gii sigooxga **aguduya ma?gidodaku*bisi**. madAxtku*tsiwAxa Abuduuxbiisii o?bigimskaa **Iyiinapsgagii matsgunadapsii** **utsspiguyiists, i_tu*dIigu agidayaku*** issxgwiip. GW190814 anistabiiw **ixinnuyiiw Iyiinapsgagii** miix itu?gutsiisdaubyuyix **notsimya negubudui** issxiimidaxin. **utsigak**~ku*daguu anI **Iyiinapsgagii, essgagani~ku*na?kgabissduutsibinaan** Abuduuxbiisii-o?bigimskaa essxgwiip amui sigooxga **udoda~ku*biisin** anu?k xistsigui: **madagagowa amu i_gitsigilists** miistsi **utsitsgago oda~ku*bii essgagani~ku*tsiya** mu?k bisaatsinsiimaan. **nimat*tsxinibinaan** amu?k **itsi_daan madAxtsiku*bij**.

gadanisdabii *ixa?ku*tsi o?ganstsiiya* Iyinibi bugutsitsbiixiya gagadusii gyi sigooxga?

amuu *ixa?ku*tsi o?ganstsiiya* Iyiniba *utspiguyisin* anistsinam anii *ixbibuyi iixsugu bugutsitsbiixiya gyi madu?g* Aganistsiip *ixa?ku*tsi sigooxga*.
Asuganistsiiw, odumu?duup a?ganisdabiiw *bugutsitsbiixiya gagadusii agitsatsiip Asabada*y mistsk *essbiguyii* anistsii Abuduuxbiisi o?bigimskaa
Iyiinapsgagii: anii ayagibuu*tsii* *iitsii_daan* itsiinAbyaa amu?k *bugutsitsbiixiya gagadusii*, anii Abuduusbiisi o?bigimskaa *Anugiyada* miixi
*aku*bugabessima arbinimya amux essbiguyii anii* *bugutsitsbiixiya gagadusii*, aganyup *niduya* anii uuma?go?gii *essbiguyi* anuum xa?gui ax~wa?subutsisuu anah *gugumiigiisi*. *udayesxgatsi*buwa, mustsk *iitsii_dan* *ixstunaduma*?guu gii madani~ku?guwAstsi anii GW190814, *anii* *essbiguyi Asabada*y igumo?bugiiw a?gitu?gwissxgwiip. anistsiiw *nidessaku*gwi*ssxiibinaan *essbiguyi* madawanikginaan mu?k GW190814 *a?ku*danistsiw* *iibuutu?*biiya anl *sigooxga* gii *bubutsitsbiixiya* gagadusii, gyi **ladugaya** *sigooxgaya*.




sinaxin *nisui*: sinaxiniists amusts *nida-pu*itu?gutsiisaduubyuyix* agooxtsiimaan (*uutsgwinatsi nayumuxtsii*) gyan utsidi?du?p (*emmixgAstsi AXIS*) mu?k o?ganabi, *gyannisti iigayissxinimya mu?* *Iyiinapsgagii aganiistinatsi*w. anii madunayiixstabinam *igitsinatsi i_tsixibiip* Astamatsugiw manistsinim itu?bugabistut*sii* *iigayissxinimya amu?k* *Iyiinapsgagii* mu?k bisaatsiinsiamaan, *imadaannistsii* anii ixtsabinam *igitsinatsi i_tsixibiip* Astamatsugiw *matsidagabiutusimya* anii *Iyiinapsgagii ino?*bugii *Axisdanitsip* mistsk *amustsk utsidomAda~kibowI* bisaatsiinsiimaan. anii nAgesstsi isxgaxix madAniip *idessuga?*gitsiip agitsxinipi *niduxge* *niduyanistsii* *nidanistsii aginsdI*si anii *ixistsabiis* awawo?biw *Asatsisaa* an?k agooxtsiimaan.

i *batsidanistsiw Aximsdanyup* manistsinim itu?bugabistut*sii* miix *bugutsitsbiixiya-gagadusii itsabiists, gyamusts essxgatsiip igagawuya bugutsitsbiixiya gagadusii* gyamustsk *babusuxbiisiists axiibiabesspsabii, essgaganigiiya* nitsuuxstuup *tsaaganisduma?*guu utsitsgago *spiguyis* amustsk *bugutsitsbiixiya gagadusii axisinotsiip*. amustsk *iigayissxinipi* *udaxiima* amuu *ixa?ku*tsi o?ganstsiiya* Iyinibiists *igumesugu ma?gidanisdapsii* *bugutsitsbiixiya gagadusii*, gii a?ganisdabiiw *sigooxga*. *Inoganistsiiw, madaganyup a?gamaabanistsiiw* amu?k GW190814 itstiwi xtu*natsisugu bugutsitsbiixiya gagadusii, gyamu?k* *axtsino?tsawo?duup* nitsuuxstuubinaan amustsk utsitsgago *a?gitstiya bugutsitsbiixiya gagadusii* igagoiists.

i_dutstsiw: tsa amu?k itsii_daan agomadabanstsiw

ibanisdabii anii sa?ku*tsi o?ganstsiiya Iyinibiists *spiguyis* itstiwi amuu *itsidugesstsii nidanistsii bugutsitsbiixiya gagadusii* gii *sigooxga issxgwiipiists*, gii bi *xanistu?bugi* anii *uuda~ga utspiguyis*. GW190814 *madanistsinum muxsk iibuutu?*biiyatsix nessxgatsimya nixii LIGO gii Virgo anu?k (satsit sinaxin nisidui). *madanistsiiwatsix* mustsk madud*Adabanistutsimya* manistsim_bya miix *ayagiibuu*?biiya o?ganstsiiya Iyinibiists anii spu?ts. *ma?ganistsis* amustsk *iibutstsiya madagagawu agitsiigiyabii agumanidanistsii iibuutu?*biya *ladugaya* *sigooxgAsts* gyi **ladugaya** *bugutsitsbiixiya gagadusii*. *amustsgogya, dAsubuyabanisdaya* amu?k *itsii_daaniix idAstuwasii ixiiigu* anu?k amustsk manistsinim itu?bugabistut*sii* amustsk *igibuu*?biiya tsanidoxuu?si ammu?k GW190814 a?gitsiglyisxiniip niitsiwa uit?guunamaanuwa *Aximsdaanists itsii_daan* amustsk gagadusii *iginab* Astutsimya mixsk *idabesspsabii*, *nidanistsiximpi_da?*binaan aasidabi spigli *gagdusiix o?gonudubya* gii ixtsists gaxsogiwa *odagiya* axinibya *odagaduumya ibwiniapsiyya* spu?tsiix *Ade~mu?siya a?gamaya~ku*su~ku?ido*dudamapsi agi~tu?gabiwi *madaganyup* miixsk *odavinatsi o?gonudubya*, *inoganistsiiw* amustsk o?ganstsiiya-Iyinibii *idAstuwasii* manistsinim itu?bugabistut*sii* axtsina~tu?issxgatsiip. amu?k o?ganabi a?ga~mu?duutstsiw gyamustsk asabu?ku?biyop amuu *itsidesstsii nadugisstsii itsii_daan*, anisdabiiw amustsk essdagaduup *iigayissxinim* amu?k a?gamanistsiiw amustsk essdagaduupiists mistsii noduyiwi *Axisdanitsip* gii o?ganstsiiya-Iyinibiists *idAstuwasii* manistsinim itu?bugabistut*sii* amustsk. gii *a?gamanisdabiiw* amu?k *ixa?ku*tsi* Iyinibii miim *itsii_daan uusdu-i* a?ga~mu?duutstsi *iibuutu?*biya o?ganabii, *utsisdabis-sugusuwa iibuutu?*biya *utsisganistsu*. gyamu?k *utsisganistsu* a?giduutsim anl *sigooxga* *aku*bugabessima* gyamustsk Abuduuxbiisi *aku*bugasuguma* *ixbigii gagadusii* *ido?ganuya* anistsk buguniists o?gonudubya. *inoganistsiiw*, madanistsiiwatsix amuux nadugisstsii abiistuut*sii*pya.

GW190814 *aku*tsisx gyamustsk spiguyiists o?ganstsiiya* Iyinibiists gii *aku*tsabop awAstamaatsugi utsibuutu?*biisnuwa. *issutsk* Abuduuxbiisi-o?bigimskaa *essxgamiiststsiiists* igagudamabiiiw agidesstamat*sugiiya* (gyi Abuduuxbiisi o?bigimskAAsts!) igagawu manistsim_bya amustsk madani~ku?guwAstsiya *iibuutu?*biya, gyamuu GW190814 *maniiw Astamatsugi*.



sinaxin nisidui: u~tu**spiguyi*isawa miistsk *bugutsitsbiixiya* gagadusiix gii sigooxgaya i ~tu**dessxgwi*pya mustsk Abuduuxbiisii o?bigimskAAsts gii *babusuxbiisii*ists *essxgatsi*ipy. anistsii *uta?*gwinatsi gii *sigumo?*xinatsi sinaxin *Astamatsugi*ya miistsk *babusuxbiisii*ists *issxgwip*siniists muuk *bugutsitsbiixiya* gagadusiix gii sigooxgaya, *maniststsi*ya, *gyannistsii* *ota?*gwinatsi gii *uutsgw*inatsi sinaxin *niduyanistsi*ya anists *issxgwip*ists i _do?gwigiyia Abuduuxbiisii o?bigimskAAsts gyamuu *Iyinapsgagii*, GW190814, *suxin*ASinuwa anii *dat*siga sinaxin amu?k *iibuu*tu?biya sigooxga gii *xisdapsxim*ya Iyinibiists *utsspiguyi*is *utsitsgu~ma?*xim, *aganyup* *nuuxgaya* nadusiix ana nadus, gyamu?k no?ganabiwi i _tu*dabissduuwa matsts*gi* sigooxga.

ibuwa?sinyow

o?ganstiyya Iyinapsgagii: *stunatsixbigii* Iyinibiists, *niduyanistsi*ya xixinatsi *bugidabi*ya, *bugutsitsbiixiya* gagadusiix gyI sigooxgaya, amustsk agomada~pstsi aku*xibAdabiyop amuu gagadusi'.

sigooxga: amuu o?ganstiyya Iyinibii *stunatsixbigii* anatsi ***mada~ku~*gudAx***igubitsabixsup anii abuduuxbiisii *Agidudwitsii_dop*.

bugutsitshiixiya gagadusi: *iixgunadapsii* *stunatsixbigii* o?ganstiyya Iyinibii Apstsiixisamuu amuu *axissiixsini_ga* amuu stundaduma?gu gagadusi.

M_{\odot} : nitsisxga nah *nadussiwa* gii anistsiiw *essxgwip*ists mu?k axiibiisabesspsabii, idumanistsiiw Adamaagidutstsi 2×10^3 0 kg.

spiguyists-iinaxigawestii: amuu iinaxigawestii sigooxga manistsim_bya i_~tuduutxinimy igago *essxgami*stsiiists miistsk o?ganstiyya Iyinibiists *utspigi*sts *itsidugesst*sii 2.5 gii $5 M_{\odot}$.

s~bii i_bugAni_gi/Abuduuxbiisii i_desstsiimobya: Abuduuxbiisii o?bigimskAAsts abatseegiiduyiya aganyup *Asstabu~ma?*gu buguniists 'bugwinatsi i _bugAni_gi.' S~bii i _bugAni_gi anis***da*banyusin** *agibuu*duutsiip *utsitsxtsii*w *nidAni_gadu*up. its*tsi*ya muustsk its*gaabi*sts *nidAni_gaduumy*a i _desstsiimobya. *igixstsga*biya, ***mad*Anuwaya** gii *igagoya* gii Abuduuxbiisiiya.

Axtsiku~bi: manisto?bi_p, amuux sigooxga *agidodaku**biya nu?gitsi nuu?gidanistsii anii matsts*gi*ya nadugisstsi nu?gadodaku*biya, anis***da*bii**w amuu gaxsogiwu nu?gado~da?bi (Axtsiku~bi) anii *udA*da~pu*bisuwa agnyup *utsitsga?*sitsiip.

anatsi-agessduuyi(ists): amuu?k anatsi niidesxgwiip tsaaganistsisamu *agitsibabawa~wa?*ga agessduuyisin, idumaanistsii aganyup gibui ixsigaasi ixsigaasi kilometers.

stunatsibyuu (Mpc): mu?k ***idu?***ganistsii myanistsibyusin idumanistsii aganyup nyuxge ixsigaasi anatsi *abawa~wa?*ga issduyiists.

mo?xinatsi agu?gitsj: *axistabawago* o?bigimskaa iix*innuyii* (mustsk *ayu?*tsipiists, anatsiists, gyI Abuduuxbiisii o?bigimskAAsts) i _do?gabiya manists*abesstsii*bi gii amuu madabi *idA*buyii. ***ni_gI*** itstsiw anisduup Doppler anis***dessts*tiw**, *agidayissts*tiwada issts*Anagaasi*, *igotsistsxku~dagu Abu?*sabesstsiiisi gii its*xisdaps*tsii *madu~ki*ixku**dagu*. *amu~gI* i _dawaniya muu *spu?ts* *Asstabu~ma?*gu, Iyinibiists imadanis*Atsii*ya gagadusiix, issts*ga*, gii *spu?tsi*sts *uutspis*siidamiss, *ayiisdap*tsiiya, gii anatsi gii matsts*gi* *babusuxbiisii*ists abatseegiiduyi i _dot*tsi*ya *ag*Asstabenuy o?bigimskaa iix*innuyii*.

oduxtsiists o?gonudubya: *gyasigutsi*piists buguniists o?gonudubya ***nobut***tsiya gagadusiix odagaduumya *spu?tsi*ix. oduxtsiists o?gonudubya its*tsi*iw aganyup ixsigaasi gagadusiix.

ibwiineedabii spu?tsiists Ade~mu?si: ixstunadess*u*guya gii ixstunad*A*byanatsi *agi~tu?*guniipy ***stats*gi**ix amustsk *spu?ts* *utsiidi*maati. anistsiya ***ixstunat***gunadabiya, ***madabo?***bi iesstuumskuutsp uutsu?guunimanuwa *spu?ts*.



Blackfoot Translation By: Sharon Yellowfly (Siksika Nation)

This Blackfoot translation of a LIGO-Virgo Science Summary was made by Sharon Yellowfly (daughter of Percy Yellowfly & Cecile Yellowfly [Sleigh] & mother of LSC member, Corey Gray). Sharon grew up in the Little Washington community of the Siksika Nation in Alberta, Canada. Blackfoot was her first language. She began working on making a Blackfoot Dictionary in the 1970s when she noticed the pool of fluent Blackfoot speakers declining and not many language resources available. Her dictionary (& the Blackfoot Pronunciation Guide below) come from her language work during her life. Her translations for the LIGO-Virgo Scientific Collaboration inspired her to continue work on her Blackfoot dictionary and update it with scientific terms.

She made her dictionary for her children.

In recent decades there has been a revitalization with Indigenous language work, and there is now Blackfoot language curriculum available and used within and outside of the Blackfoot Confederacy of Alberta/Montana. You will notice variations in this current curriculum and Sharon's dictionary. Sharon made her dictionary utilizing her B.A. in Anthropology & background in linguistics. Sharon's dialect & translation come from both "old style" & contemporary Blackfoot; additionally, it will be how it is spoken in a dialect/accent from Little Washington in Siksika Nation. Sharon is very happy to see the resurgence in Blackfoot language, and is very proud of all the teachers teaching our language to Blackfoot youth.

Blackfoot Pronunciation Key For Vowels, & Other Symbols:

<u>BLACKFOOT</u>	<u>ENGLISH</u>
a	<u>father</u>
i	<u>eat</u>
u	<u>book</u>
e	<u>let</u>
o	<u>go</u>

x - <u>six</u>	?	- glottal stop
A - <u>acorn</u>	-	- as in ' <u>he</u> ' but held a little longer
I - <u>ice</u>	*	- <u>who</u>
	~	- (not quite a full glottal stop) as in ' <u>cotton</u> '
[bold & italics]		- inflection